NEWS RELEASE

TRUMBULL COUNTY ENGINEER

650 NORTH RIVER ROAD N.W. WARREN, OH 44483

FOR IMMEDIATE RELEASE: **January 13, 2026**

TRUMBULL COUNTY

UPCOMING PROJECT INFORMATION TRUMBULL COUNTY ENGINEER PROPOSES SIDEWALK IMPROVEMENTS ALONG MAIN STREET (STATE ROUTE 5/7) AND KINSMAN NICKERSON ROAD IN KINSMAN TOWNSHIP

PID: 122896

Trumbull County Engineer, David DeChristofaro, in cooperation with Kinsman Township, proposes to install 5-foot-wide concrete sidewalk along the east side of Main Street (State Route 5/7) from Lakeview Drive north to State Route 87, a distance of 1,311 feet. Additionally, the project proposes the removal and replacement of existing deteriorated 4-foot-wide concrete sidewalk on north side of Kinsman Nickerson Road from State Route 5/7 to Garden Street, a distance of 335 feet. The proposed sidewalk project will link residential neighborhoods and businesses within the area.

Further improvements proposed by the project include linear grading, storm water drainage improvements including catch basin reconstruction or replacement and conduit replacement, new concrete curb ramps/truncated domes/detectable warning installations to comply with Americans with Disabilities Act (ADA) standards and the application of new stop lines/crosswalk lines, as necessary throughout the project limits. No new permanent and/or temporary right-of-way is needed to construct the project.

The proposed $228,170 sidewalk project is scheduled to begin construction in the summer of 2026. During project construction, a minimum of one lane of traffic shall be maintained along Main Street and Kinsman Nickerson Road, however, temporary lane restrictions will be necessary and accomplished utilizing flaggers. Road closures and detours are not proposed to construct the project. All necessary signage will be posted within the project construction limits and all intersection side roads. Access shall be maintained to all adjacent properties, businesses and intersecting side streets for the duration of the project.

As part of the environmental process for the project, Trumbull County Engineer, David DeChristofaro, is seeking any comments the public may have regarding the social, environmental and economic impacts of this proposed project. Project-related issues the

public may wish to comment on include, but are not limited to, the effect of the project on residents, the local economy, and historic or cultural resources.

Any questions or comments concerning the proposed project should be directed to Mr. Gary W. Shaffer, P.E. by February 13, 2026, at the Trumbull County Engineer's Office, 650 North River Road N.W., Warren, Ohio 44483, by electronic mail at hwshaffe@co.trumbull.oh.us or by telephone at 330-675-2640.